

OCTOBER 3, 2017

Client: **Cumberland County Schools**
Project: **Douglas Byrd HS Tennis Courts Replacement**
Project No.: **17004**

Designer:
Crawford Design Company
116 N. Cool Spring Street
Fayetteville, NC 28301
Ph.: 910.221.0033
Fx.: 910.221.0035



All provisions of the contract documents including the technical specifications, general conditions and contracts apply to the work unless modified by the addendum.

GENERAL

- 1. Are Performance/Payment Bonds required? IFB page 1 indicates that they are not required, but page 0200-4 indicates that they are require. Please clarify.**

Response: Yes, performance and payment bonds are required.

- 2. At Byrd H.S., any idea how deep the 8" RCP is buried? Is this an abandoned line, or is it still attached to drain structures?**

Response: Contractor shall remove Existing YI1 and install new yard inlet approximately 5 feet from new sidewalk. Invert out elevation of 12-inch shall be 193.5. Install 50 feet of 12-inch PVC line from YI1 to new DI1 at an invert elevation of 192.00. Existing 12-inch line shall be filled with a minimum to 2 feet of concrete.

- 3. At Byrd H. S., Drawing C0.1 Demo #9 indicates cutting and filing 12" RCP pipe to dimensions shown. Please clarify what you mean by this - the dimensions are not apparent - not sure what you want here.**

Response: Fill ends of pipe a minimum of 2 feet with concrete.

- 4. Same drawing - Demo note #6, remove existing yard drain and all associated components. Does this include removal of any pipe or just the drain structure itself?**

Response: The yard drain shall be completely removed. The associated storm drain shall be filled with concrete for at least two feet to provide a seal.

- 5. All storm drainage piping shall be smooth wall HDPE.**