

PROJECT: Pauline Jones School
225 "B" Street
Fayetteville, NC 28301

ADDENDUM 02
DATE: 04-04-19

OWNER: Cumberland County Schools

BID DATE: 04-17-19
TIME: 11:00am

VIA: EMAIL TO ALL BIDDERS

ARCHITECT: THOMAS GOETZ (910-485-3000) t.goetz.architect@gmail.com

This Addendum is issued prior to receipt of the bids and shall and does hereby become a part of the drawings, specifications and project manual for the project. All principal contractors shall be responsible for seeing that their subcontractors are properly appraised of the contents of this addendum. All information in the addendum shall supersede and take precedence over any conflicting information in the original drawings, specifications and project manual.

All contractors shall acknowledge receipt of the addendum.

The following changes, additions and clarifications are made to the drawings and project manual for the above referenced project. 1 page

GENERAL / PROJECT MANUAL

1. A separate heavy duty fusible disconnect shall be provided for each new piece of mechanical equipment. An internal unit mounted disconnect will not count as the disconnect means.
2. All exterior conduit shall be rigid. All new interior conduit shall be EMT. A limited amount of liquid tight flexible conduit shall be used for connection to equipment.



END OF ADDENDUM NO. 02